VertivTM GeistTM rPDU



OVERVIEW

Upgradeable Unit Level EC Monitored rPDUs provide reliable power distribution to critical IT equipment while delivering a comprehensive view of input level power usage via remote network access. Includes environmental monitoring capabilities to obtain realtime environmental metrics. Upgrade the hot-swappable monitoring device on select units to leverage new technologies and accommodate changing business needs.

Benefits

- Reliable power distribution with local and remote power monitoring options offer quick access to critical power usage information to evaluate energy usage trends and maximize uptime.
- **Environmental monitoring** capabilities with the addition of optional environmental sensors ensure users have critical infrastructure data at their fingertips to prevent climate-related equipment failure and system downtime.
- Fault-Tolerant Daisy Chaining with RSTP simplifies intelligent rPDU connectivity and ensures data is reported even when a breakin the network chain occurs. Supports up to 40 rPDUs.
- Every unit is 100% tested for reliability and functionality.
- Daisy-chain up to 50 devices on a single IP address and reduce deployment time with selfconfiguration of downstream devices.

Part #: UI30005L

Model Number: DU03E2R1-18PB67-2S02A9F00-S Category: Monitored Sub Category: Unit Level Power Configuration: Variable, Variable, 22.0kW Physical Configuration: 19in / 483mm, Horizontal

Product Summary:

rPDU, Monitored Unit Level EC, 22.0kW, Variable Power Configuration, Horizontal, (12) Locking IEC C13, (6) Locking IEC C19, Universal Inlet, Black Powder Coat.

Monitoring:

Input and per Phase power monitoring with Circuit/Breaker current monitoring. Environmental monitoring via optional remote sensors. Daisy chain Ethernet connectivity. Local high visibility display.

Plug Form:

Receptacle:





Universal Inlet

Locking IEC C13 Locking IEC C19 (Quantity: 6)

Chassis Color Options:



To discuss color options, contact your local sales representative.

(Quantity: 12)

Product Specification and Options

System Features

Monitoring

Input and per Phase power monitoring with Circuit/Breaker current monitoring. Environmental monitoring via optional remote sensors. Daisy chain Ethernet connectivity. Local high visibility display.

Vertiv.com | Vertiv Headquarters, 505 N. Cleveland Avenue, Westerville, OH, 43082, USA

© Vertiv Group Corp. All rights reserved. Vertiv[™], and the Vertiv logo are trademarks or registered trademarks of Vertiv Group Corp. All other names and logos referred to are trade names, trademarks or registered trademarks of their respective owners. While every precaution has been taken to ensure accuracy and completeness here, Vertiv Group Corp. assumes no responsibility, and disclaims all liability, for damages resulting from use of this information or for any errors or omissions. Specifications, rebates and other promotional offers are subject to change at Vertiv's sole discretion upon notice.

| Input Monitoring | Total Unit Monitoring (kWh, W, VA, PF) Phase Monitoring (kWh, W, VA, PF, V, A) |
|---|--|
| | Power Measurements Compliant with ANSI C12.1 and IEC 62053- 21 at 1% Accuracy Class Requirements |
| Quantity Of Inputs | 1 |
| Maximum Input Power (Defined by Facility Side Cable) | 63A Single Phase, 240V Max, 14.4kW 48A 3 Phase DELTA, 240V Max, 19.9kW 32A Three Phase WYE, 240/415V Max, 22.0kW |
| Frequency | 50/60Hz |
| Over Current Protection | (6) 16A Double Pole Magnetic Breakers (10kAIC Rated) |
| Switch | Breaker/Switch Combination |
| Scrolling / Rotatable Digital Display | Yes |
| Power Entry Location | Right Rear |
| Plug Type | Universal Inlet |
| Combined Total Receptacle/Socket Quantity | 18 |
| Receptacle/Socket Type #1 | U-Lock IEC C13 |
| - Quantity on Face | 12 |
| - Quantity per Breaker | 2 |
| - U-Lock Color ID | 6 Circuit = Orange, Green, Blue, Light Orange, Light Green, Light Blue |
| - Style | Individual |
| - Voltage per Receptacle/Socket | Defined by Facility Side Cable |
| Receptacle/Socket Type #2 | U-Lock IEC C19 |
| - Quantity on Face | 6 |
| - Quantity per Breaker | 1 |
| - U-Lock Color ID | 6 Circuit = Orange, Green, Blue, Light Orange, Light Green, Light Blue |
| - Style | Individual |
| - Voltage per Receptacle/Socket | Defined by Facility Side Cable |
| Internal RMS Voltage Sensor | Yes |
| Internal RMS Current Sensor | Yes |
| Network Connection | Dual 10/100/1000Mbps Ethernet |
| Protocols Supported | DHCP, HTTP, HTTPS, IPv4, IPv6, LDAP, NTP, RADIUS, RSTP, SSH, SMTP, SNMP (v1/v2c/v3), Syslog, TACACS+, Modbus TCP |
| Data Access Formats | CSV datalog, JSON API, JSON datalog |
| USB Support | Yes |
| IP Reset Button | Yes |
| Hard Reboot Button | Yes |
| Serial Connection | RS232 via RJ45 |
| Remote Sensor RJ Connection Jacks | 1 (Supports up to 16 Sensors) |
| Maximum Operating Temperature | 60C / 140F |
| Heavy Steel - Powder Coat Finish | Black |
| Configuration | 2U |
| 19in Recess Mount | Yes |
| | |

Vertiv.com | Vertiv Headquarters, 505 N. Cleveland Avenue, Westerville, OH, 43082, USA © Vertiv Group Corp. All rights reserved. Vertiv ", and the Vertiv logo are trademarks or registered trademarks of Vertiv Group Corp. All other names and logos referred to are trade names, trademarks or registered trademarks of their respective owners. While every precaution has been taken to ensure accuracy and completeness here. Vertiv Group Corp. assumes no responsibility, and disclaims all liability, for damages resulting from use of this information or for any errors or omissions. Specifications, rebates and other promotional offers are subject to change at Vertiv's sole discretion upon notice.

| Product Warranty | 5-year limited warranty if registered within 120 days of purchase, otherwise warranty defaults to 3 years |
|--------------------------------|---|
| Certification/Agency Approvals | CE Marked |
| Certification/Agency Approvals | UKCA Marked |
| Certification/Agency Approvals | Complies with IEC 62368-1 (DOC Available) |
| Certification/Agency Approvals | Complies with EN 55032 and EN 55035 |
| Certification/Agency Approvals | RoHS Compliant |
| Certification/Agency Approvals | FCC Part 15 Class A Conformance |
| Certification/Agency Approvals | Cم Mark |
| Certification/Agency Approvals | RCM Mark (EMC Only) |
| Certification/Agency Approvals | China RoHS |
| Certification/Agency Approvals | UL & c-UL Listed 62368-1 |
| Chassis Dimensions (HxWxD) | 3.39in x 17in x 9in / 87mm x 432mm x 229mm |
| Shipped Weight | 16lbs (7.26kg) |
| | |

Vertiv.com | Vertiv Headquarters, 505 N. Cleveland Avenue, Westerville, OH, 43082, USA © Vertiv Group Corp. All rights reserved. Vertiv ", and the Vertiv logo are trademarks or registered trademarks of Vertiv Group Corp. All other names and logos referred to are trade names, trademarks or registered trademarks of their respective owners. While every precaution has been taken to ensure accuracy and completeness here. Vertiv Group Corp. assumes no responsibility, and disclaims all liability, for damages resulting from use of this information or for any errors or omissions. Specifications, rebates and other promotional offers are subject to change at Vertiv's sole discretion upon notice.